Approximate estimate of quantities for labour portion of the work for improving the Distribution System of Hole-Narasipur Water Supply.

No.	Particulars	Unit	Quantity
	Labour Charges.		
1	Earthwork excavation including refilling and consolidation, etc., complete	C.yd.	695
2	Laying and lead jointing C. I. pipes 4″ bore, including fixing C. I. sluice valves, with flanged joints with bolts, nuts and rubber insertion, etc., complete	Each Joint	147
3	Laying and lead jointing C. I. pipes 3″ bore	,,	174
4	Removing and relaying G. I. pipes with fresh trench, cutting, including refilling the existing trench, etc., complete ¾″ pipe	R.ft.	655
5	Do do do 1″ bore	,,	817
6	Laying and jointing of G. I. pipes with fresh trench cutting, including refilling, etc., complete .. .. 1½″ size	,,	895
7	Do do do do 1″ size	,,	1,377
8	Do do do do ¾″ size	,,	2,243
9	Construction of gland cock cisterns as per type design including fixing C. I. road boxes for formation of cement pillets, etc., complete	Each	22
10	Construction of public fountain platforms 4′×4′ interior, as per type design	,,	15
11	Construction of masonry valve cistern 2½′×2½′ interior as per type design	,,	5
12	Absorption pits 6′×6′×6′ with jelly and brick bats	,,	2

N. KRISHNIENGAR,
Sanitary Engineer.

TUMKUR DIVISION.

Abstract Notification dated 23rd June 1939.

The attention of the public is drawn to the notifications calling for tenders for Constructing Staff Quarters and Office Buildings, etc., for Electrical Department at Kunigal Town published in pages 1237-1242, Part VI of the *Mysore Gazette*, dated 29th June 1939.

Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 17th July 1939.

The earnest money required for the work is Rs. 462, which should be credited to the Treasury under the head "17 (*a*) P. W. Deposits" and challan enclosed.

Abstract Notification dated 28th June 1939.

The attention of the public is drawn to the notification calling for tenders for " Opening out a feeders channel from Suvarnamukhi river to Lakshmipur tank, Reg. No. 40, Madhugiri Taluk" published on pages 1284-1285, Part VI of the *Mysore Gazette*, dated 6th July 1939.

Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 24th July 1939.

The earnest money required for the work is Rs. 545 which should be credited to the treasury to the head "17 (*a*) P. W. Deposits" and chellan enclosed with the tender.

Notification dated 4th July 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M., on 29th July 1939, for Increasing the capacity of Kodagadala Tank, Reg. No. 231, Madhugiri Taluk. An approximate estimate of quantities is given below. These quantities are no guaranteed. The work should be completed by the end of October 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained by paying Re. 0-4-0. from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury challan for Rs. 180 for having credited to " 17 (*a*) P. W. Deposits " as earnest money and be superscribed " Tender for Increasing the capacity of Kodagadala Tank, Madhugiri Taluk " in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent o r contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract of estimate for increasing the capacity of Kodagadala Tank, Registered No. 231, Madhugiri Taluk.

Item No.	Description of work	Per	Rate	Quantity	Total
			Rs. a. p.		
	BUND.				
1	Earthwork-to bund with watering and tamping ..	C.yds.	0 4 0	5,719	
2	Turfing	S.yd	0 1 0	10,893	
3	Cutting grips in the old bund	R.yd.	0 0 2	3,675	
4	New stone revetment	L.S.			
	WASTE WEIR.				
1	Earthwork in foundation	C.yd.	0 4 0	104	
2	Concrete in surki mortar	C.ft.	0 4 0	777	
3	Burnt brick in surki mortar	C.ft.	0 4 6	1,243	
4	Burnt stone slabs 6" thick	S.ft.	0 6 0	577	
5	Removing and refixing in mortar old coping slabs ..	S.ft.	0 2 0	112	
6	Plastering with surki mortar	Sqr.	3 12 0	9·56	
7	New stone sujicut work	C.yd.	1 8 0	124	
8	Scraping old plaster, dismantling brick masonry to join the new skin wall, etc.	L.S.			
9	Earthwork embankment	C.yd.	0 3 6	265	
10	Compensation for lands for the extension of the weir and raising the revetment wherever necessary ..	L. S.			

Notification dated 8th July 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 29th July 1939, for Restoring the breached Kalenahalli Gangammankere, Reg. No. 209, Sira Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained by paying Re. 0-4-0 from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury chellan for Rs. 290 credited to "17(*a*) P. W. Deposits," as earnest money, and be superscribed "Tender for Restoring the breached Kalenahalli Gangammankere, Sira Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per current schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words, as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than the estimated rate will not be accepted.

Abstract estimate for restoring breached Kalenahalli Gangammankere Tank, Registered No. 209, Sira Taluk.

Item No.	Description of work	Per	Rate	Quantity	Cost
	BUND.		Rs. a. p.		Rs.
1	Jungle clearing in breach No. 1 and 2	L. S.	..	..	
2	Clearing sand and silt	C.yd.	0 2 6	3,844	
3	Baling out water	L. S.	..	..	
4	Excavating temporary wells in the bed for watering the earth	,,	..	..	
5	Earthwork, cutting trenches, foundation of puddle wall	C.yd.	0 2 6	526	
6	Earthwork embankment from excavated stuff ..	,,	0 1 6	526	
7	Puddle core wall	,,	0 8 0	813	
8	Earthwork to bund with watering, tamping including load and lift	,,	0 5 6	7,880	
9	Turfing front and rear slopes	S.yd.	0 1 0	1,704	
10	Old rough stone work with new jelly	C.yd.	0 12 0	50	
11	New rough stone work	,,	1 8 0	573	
12	Gravel backing	,,	0 6 0	191	
13	Cutting and filling up old bund in rear	L. S.	..	..	
14	Painting old grade stones	Each	0 4 0	18	
15	New grade stones with figuring and painting fixed in position	,,	2 4 0	6	
16	Do B. M. stones	,,	2 8 0	2	
17	Do Registered No. stone	,,	4 0 0	1	
	SLUICE.				
1	Sundry repairs to sluice	L. S.	..	..	
2	Providing plug and rod with locking arrangement ..	,,	..	..	
	WASTE WEIR.				
1	Extending the present weir without apron by 36 feet draft and approach clearing, making good damage to body wall and apron	..	..	..	
1	Earthwork excavation in gravelly soil (only lead charges of ½ furlong paid)	C.yd.	0 2 0	651	
2	Do soft rock	,,	0 7 0	21	
3	Dismantling old masonry	C.ft.	0 0 6	32	
4	Burnt brick in surki mortar	,,	0 5 0	80	
5	Burnt stone slabs 6" thick	S.ft.	0 7 0	210	
6	Fixing old burnt stone slabs in surki mortar ..	,,	0 2 0	90	
7	Plastering with surki mortar	Sqr.	3 12 0	2	
8	Cutting Joggles	No.	1 0 0	15	
9	Resetting old stone work with new jelly	C.yd.	0 12 0	117	
10	Filling in scours with big jelly	,,	0 8 0	15	

P. RAJAGOPALAN,
Executive Engineer.